

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64


No:EE/YNK-D/E-PMT/19/2022-23 Dt:14-03-2023


APPROVED TENDER SCHEDULE - 'B'

Item 02

Name of Work:-Construction of CC roads in Attur ward no :04 Yelahanka Satellite town sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri. AKSHAY KUMAR H B (AKSHAY CONSTRUCTIONS)	
				Rate	Rate in Words
1	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials	Cum	195.45	464.00	Four Hundred SixtyFour Only
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately) Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates	Cum	117.38	6109.00	Six Thousand One Hundred Nine Only
3	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., complete. as per the directions of the Engineer	Cum	117.38	7163.00	Seven Thousand One Hundred SixtyThree Only
4	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km	t.Km	410.46	105.50	One Hundred Five Paise Fifty Only


Signature of the Contractor


Executive Engineer
Yelahanka Division,
BBMP, Bengaluru-64.
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064